

# IFMIF-DONES Industrial Opportunities



**P. Cara** (DONES Programme Manager)



Dutch Fusion Day  
Eindhoven, May 8<sup>th</sup> 2026

# Why IFMIF-DONES ?



One of the main differences between **ITER** and **DEMO** is the radiation dose: at DEMO more than **one order of magnitude higher**



# What is IFMIF-DONES?

Challenging!!!

An accelerator-based fusion-like neutron source required for the qualification of the materials to be used in the DEMO reactor




A neutron flux of  $\sim 10^{15} \text{ n/cm}^2/\text{s}$  is generated with a neutron spectrum up to 55 MeV energy

Identified as **high priority** in the EU Fusion Roadmap  
Included in the **ESFRI Roadmap** as EU strategic facility

# DONES Programme Timeline


## DONES Programme Phases

The objective of the DONES Programme is not only for building the IFMIF Facility... but also to operate and to exploit it!!






# DONES Programme Timeline



## DONES Programme Schedule



**Critical path milestones**

• Project "start"	T0
• Initial team build up	+1 y
• Site preparation contract	+1 y
• Buildings and Plant Systems contract	+2 y
• Building ready	+6 y
• Injector contract	+4 y
• Injector installation	+6 y
• RFQ contract	+4 y
• RFQ installation and commissioning	+7 y
• SRF linac contract	+5 y
• Start of SRF installation and commissioning	+8 y
• DONES (integrated) commissioning	+10 y
• Start of DONES operation	+11 y


Aim is DONES Programme, not only the IFMIF-DONES Facility

## The DONES Programme includes:

- The construction and **operation** (including running the irradiation experiments) of the DONES Facility
- The preparation of **irradiation** experiments (**for fusion but also other applications**)
- The analysis of the **irradiation** results
- The development of **a qualified irradiation database**, and of the required modelling and extrapolation capabilities


On-site

Off-site




**Applications for fusion and for other scientific areas**  
(radioisotopes production for medical applications, nuclear physics, industrial applications)

# IFMIF-DONES Experimental Capabilities



# DONES-ConP1 Fusion Experimental Plan




**Several irradiations campaigns will be needed!!!**

Priorities to be defined

Loading flexibility will be important

Reloading capability will be also implemented



## Is it possible to speed up?

- Most effective way: add second Accelerator (x2 faster from 2035)
- Some improvement: additional parallelization of the construction and commissioning phase
- Some improvement: Implementation of some optional upgrades

# 6th DONES Steering Committee held on 21/11/25

## DONES-SC Parties (after MIDA signature):

- *IFMIF-DONES España (Spain)*
- *RBI (Croatia)*
- *QST (Japan)*
- *F4E (European Commission)*
- *INFN (Italy)*

## DONES-SC Observers:

- *Austria*
- *Belgium*
- *Czech Republic*
- *Finland*
- *France*
- *Germany*
- *Hungary*
- *Latvia*
- *Lithuania*
- *Romania*
- *Slovakia*
- *Slovenia*
- *Ukraine*



## Agreements reached:

- *Key Governance and Management documents agreed.*
- *Reference document for Cost estimation for the DONES Programme agreed (“Value estimated for DONES Programme phases”).*
- *Establishment of the DONES Programme Team & Programme Manager*
- *Draft Procurement Agreement template ready*
- *Outcome of the DONES Baseline review and recommendations*
- *IP rules agreed (at least partly)*

## DONES Programme Mission


The mission of the DONES Programme is to develop a database of fusion-like neutron irradiation effects in the materials required for the construction of fusion power reactors

## DONES Programme Objectives

- To provide a neutron source producing fusion-like neutrons at sufficient intensity and irradiation volume.
- Generate materials irradiation test data for DEMO.
- Generate data base for benchmarking with computational material science.
- To develop a "Complementary Experiments" work program.

## The IFMIF-DONES Facility

The fusion relevant neutron source and that will allow to fulfill the objectives of the Programme.



- Project run by flexible Programme Team and relying on In-Kind Manpower contributions from different partners.
- Design Authority with the Programme Team.
- Owner/Operator responsibility on the Spanish Legal Entity.

# Site Status



Escúzar (18 Km from Granada)








# IFMIF-DONES: Backed by IFMIF-EVEDA & WPENS

Engineering Design IFMIF Intermediate Engineering Design Report (2013) ✓



## Engineering Validation



Test Facility (2015) ✓


Target Facility (2017) ✓

Linear IFMIF Prototype Accelerator (LIPAc)  
9 MeV, 125 mA CW, 1.125 MW (36 m)

Phase A (2017) ✓


Phase B (2019) ✓

Phase B+ (2024): 5 MeV, 118 mA, 10% duty cycle ✓



DONES Plant Description Document (07/2023) ✓

# DONES In-Kind Contribution Framework



# Site, Buildings and Plant Systems

**1 Main Building**

Housing of all irradiation systems (Accelerator, Lithium & Test Systems)

**Auxiliary Buildings**

**2 Main Building Access Bldg**



- 3** Main Electrical Bldg
- 4** Electrical Switchyard Bldg
- 5** Emergency Power Bldg (Train A)
- 6** Emergency Power Bldg (Train B)
- 7** Cooling Towers & Chillers Electrical Bldg

EPS [Electric Power System]

- 8** Water Treatment Plant  
SWS [Service Water System]
- 9** Boiler for HVAC
- 10** Chillers & Pumps Bldgs for HVAC  
HVAC System

- 11** Cooling Towers Bldgs  
HRS System [Heat Rejection System]

- 12** Fire Water Pumps Bldg  
FPS [Fire Protection System]

- 13** Empty Casks Storage Area  
RWTS [Radioactive Waste Treatment System]

- 14** Service Gas Areas  
SGS [Service Gas System]

- 15** Administration Bldg
- 16** Access Gate Bldg
- 17** Warehouse

Under Construction


**Estimated Value Range**




- A** Less than 2M
- B** Between 2M and 5M
- C** Between 5M and 10M
- D** Above 10M




# Site, Buildings and Plant Systems




# Site, Buildings and Plant Systems



Heat Rejection System





Water Treatment Plant



Warehouse

Electric Power System




Access Gate



Administration Building



HVAC Systems




Service Gas System

# Accelerator Systems


Accelerator based on IFMIF design with

Beam incident at 9° angle →

possibility to upgrade to IFMIF with 2<sup>nd</sup> mirror accelerator (10 MW)




## Beam footprint @ target



20x5 cm<sup>2</sup> footprint (reference)

10x5 cm<sup>2</sup> footprint (optional)




D+ CW 175 MHz SC LINAC  
 125 mA / 40 MeV → **5 MW**  
 Total length of ~100 m  
 Windowless liquid Li target  
 20 y, 87% availability  
 Hands-on maintenance (<1 W/m)

# Accelerator Systems (Injector)


Based on LIPAc design and commissioning (117 mA / 5 MeV / 8.75% DC)

140 mA Continuous Wave deuteron beam at 100 keV  
Electron Cyclotron Resonance ion source

Injector enhancement based on LIPAc operational feedback in the frame of IFMIF/EVEDA




## Injector Design Risks



# Accelerator Systems (Injector)

## Needed Skills / Key Technologies



**B**

### Estimated Value Range

- A** Less than 2M
- B** Between 2M and 5M
- C** Between 5M and 10M
- D** Above 10M




Based on LIPAc design and commissioning (117 mA / 5 MeV / 8.75% DC)

## RFQ

- **Vanes erosion model** based on sputtering.  
Other phenomena under study (ion implantation, ...)
- **RFQ mechanical engineering upgrade** to ease the maintenance
- **Power coupler with brazed windows** under prototyping



## Project Risks: Transmission Factor Failure



**Optimal Neutron Levels  
Not Maintained**

System effectiveness is significantly challenged



**Transmission Factor Not  
Achieved**

Neutron flux is insufficient

## Needed Skills / Key Technologies



### RF Source Expertise

Knowledge in generating radio frequency



### Beam Dynamics Modelling

Skills in simulating particle beam behavior



### Mechanical Machining

Proficiency in shaping and assembling components



### High Voltage and Electronics

Understanding of electrical systems




### Instrumentation for Diagnostics

Experience in measuring and monitoring

#### Estimated Value Range




- A Less than 2M
- B Between 2M and 5M
- C Between 5M and 10M
- D Above 10M




# Accelerator Systems (Medium Energy Beam Transport)

Based on LIPAc design and commissioning (117 mA / 5 MeV / 8.75% DC)



**MEBT Beam Shaping**  
Inability to shape beam as required

**Excessive Scraper Losses**  
Beam losses go undetected



## MEFT

- Modifications to improve the **maintainability**
- Enhancement of the **Beam Diagnostics** (DC measurement) and **Vacuum package**

## Needed Skills / Key Technologies



**RF Source Proficiency**

Understanding and utilizing RF sources



**Beam Dynamics Modelling**

Optimizing particle behavior



**Mechanical Machining**

Precise fabrication of components



**High Voltage and Electronics**

Safe handling of electrical systems



**Instrumentation for Diagnostics**

Monitoring and analyzing system performance




**Estimated Value Range**

- A Less than 2M
- B Between 2M and 5M
- C Between 5M and 10M
- D Above 10M




# Accelerator Systems (SRF LINAC)

- **Five Cryomodules** top-loaded → integration in the vault
- Two types of HWR's cavities: 19 x low- $\beta$  and 27 x high- $\beta$
- <200 kW RF couplers. Biased T-box design
- **29 x solenoids packages** (with steerers, BPM's & BLM's)
- **4 x Short Warm Sections**
- Complete study of **cryogenic hazards**
- **Studies of assembly and transport**
- **Prototyping and tests of cavities, RF couplers and microloss monitors**



## System Risks and Challenges



**FUSION  
FOR  
ENERGY**



**INFN**  
Istituto Nazionale di Fisica Nucleare

# Accelerator Systems (SRF LINAC)

## Needed skills / Key Technologies



**Simulation and Design**

Creating blueprints and models



**Estimated Value Range**

- A Less than 2M
- B Between 2M and 5M
- C Between 5M and 10M
- D Above 10M



**Material Procurement**

Sourcing specialized materials



**Cryogenic Component Design**

Engineering cooling systems



**Machining**

Shaping components with precision



**Cleanroom Assembly**

Assembling in a sterile environment



**Solenoid Manufacturing**

Producing and testing solenoids




**Cavity - Coupler**



**Solenoids**




Beam Dump



- **Multipole magnets** (oct/dodec) for rectangular shape
- **Beam Dump** for commissioning and tuning
- Safety-credit and machine protection **Fast valves**
- **Aluminium beampipe** to minimize the activation
- CuCrZr water-cooled RH **Scraper**
- RH He-cooled **Collimator** at TIR
- 1% DC RH **Beam Dump** (LIPAc modified design)
- **Beam diagnostics** for all beam modes → prototypes and tests of critical diagnostics in TIR area (such as profile monitors)
- **Argon cold trap** in the main beamline
- Secondary beamline for **IFMIF upgrade** with **target diagnostics**
- Possibility of **beam extraction** under assessment




## Beam Shaping and Physics Risks




**Beam Physics Complexity**  
Complicates understanding and manipulation

**Beam Shaping Problems**  
Inefficiencies and inaccuracies



**Beam Profile Monitor**




**AC-CT**

### Estimated Value Range




- A Less than 2M
- B Between 2M and 5M
- C Between 5M and 10M
- D Above 10M



## 56 RF Stations to supply the RFQ (8), MEBT (2) & SRF (8;11;9;9;9) cavities including the respective coaxial lines

- Based on **SSPA** (LIPAc Tetrode Based) to improve the reliability and maintainability
- The design of the RF System well advanced by improving the **efficiency** (>60%) and architecture with respect to the LIPAc one
- Requirements for a powerful **LLRF** based on LIPAc experience
- Challenging design of the **coaxial lines**
- Assessment of **circulator** requirements and **transistors** technologies
- Several prototypes have obtained so far 200 kW CW w/ hydrid combiners or 100 kW CW w/ cavity combiners

## EMC and Component Supply Chain Risks



**Component Supply Chain**  
High number of components needed

**EMC Radiated Emissions**  
Limits exceeded at 175 MHz



# Accelerator Systems (RF Power System)

## Needed Skills / Key Technologies



**Power Amplifier Technology**

Enhances signal strength



**Circulator Technology**

Ensures unidirectional signal flow




**Coaxial Line Technology**

Minimizes signal loss

### Estimated Value Range


- A Less than 2M
- B Between 2M and 5M
- C Between 5M and 10M
- D Above 10M

**D**



16 kW up to **200 kW**  
**CW 175 MHz** RF Power System  
**12 MVA** electric consumption

# Accelerator Systems (Accelerator System Ancillaries)



**FUSION  
FOR  
ENERGY**

# Accelerator Systems (Accelerator System Ancillaries)

## Needed Skills / Key Technologies



### Electrical Distribution

Power management and engineering



### Water Cooling

Temperature maintenance



### Vacuum Technologies

Industrial applications



### Gas Distribution

Safe and efficient gas management



### Cryogenic Production


Low-temperature processes

### Estimated Value Range

- A Less than 2M
- B Between 2M and 5M
- C Between 5M and 10M
- D Above 10M

D

## Project Integration Risks



**Overall Integration**  
Complexities of system integration


**Interface Management**  
Coordination between components

**Target System** : devoted to creating and steadily maintaining a liquid lithium jet with the required characteristics in front of the D+ beam (footprint 20 x 5 or 10 x 5 cm<sup>2</sup>)

Estimated Value Range


- A Less than 2M
- B Between 2M and 5M
- C Between 5M and 10M
- D Above 10M

**D**




**Main risks:**

- High Levels of impurity in Li Impurity Control System
- Assembly under operational conditions
- Tritium Desorption in Lithium Traps due to limited research and uncertain performance



Li jet



**Characteristics:**


- Connected to the Beam line
- Li jet speed: 15 m/s
- Li jet thickness: 25 mm
- Removed power: ~ 5 MW
- Li working temperature: 300 °C

# Test Systems (Test Cell, Irradiation Modules, Ancillaries)




**Testing and understanding the degradation of the materials and components properties throughout their operational life in DEMO and future fusion power plants**

- Fluences of 20-30 dpaNRT in less than 2.5 years applicable to 0.3 litre volume and fluences of 50 dpaNRT in less than 3 years applicable to 0.1 litre volume
- Temperature range: 250 - 550 °C; temperature gradient < 3%
- High-flux region: Up to  $5e^{14}$  n/cm<sup>2</sup>/s fast-neutron flux (> 10 MeV)


**Main risk:**  
- Failure of critical functions in irradiation systems due to the harsh neutron and temperature environment during irradiation campaigns



- 120 specimens per capsule
- Around 1000 specimens in the high-flux region
- Almost 3000 specimens per irradiation campaign




- Estimated Value Range**
- A Less than 2M
  - B Between 2M and 5M
  - C Between 5M and 10M
  - D Above 10M



**STUMM**


- Key role during the commissioning with beam and target
- Benchmarking of the neutronics models of the neutron and gamma fields
- Filled with tens of ionization chambers, micro-fission chambers, SPNDs (Self-Powered Neutron Devices), gamma thermometers and activation specimens

# Remote Handling Systems



Telescopic mast crane  
Robotic Arm

## Viewing Systems




## Estimated Value Range

D

- A Less than 2M
- B Between 2M and 5M
- C Between 5M and 10M
- D Above 10M



FUSION  
FOR  
ENERGY




## Cranes + Robotic Arms

Gripper system  
3 t capacity  
8 m crane span

## Multipurpose system for High Flux Test Module



Total absorbed dose  $\sim 1$  MGy  
Precision  $< \pm 1$  mm  
Payload 2t




## Decontamination Stations



# Central Instrumentation and Control Systems



## Project Integration Challenges



**Integration Complexities**  
Seamless integration processes


**Interface Management**  
Coordination between components



### Estimated Value Range

- A Less than 2M
- B Between 2M and 5M
- C Between 5M and 10M
- D Above 10M**





## • OBJECTIVES:


- ✓ SAFETY
- ✓ AVAILABILITY
- ✓ EFFICIENCY

## • REQUIREMENTS:

- ✓ Long Stop (480h) and Short Stop (3 days) along 1-year irradiation
- ✓ Systems availability exceeding 90% is needed to achieve the overall goal of 70% availability for DONES


## PLANNED MAINTENANCE (PM)

- **NO FAULT DETECTION:** Preventive / Condition-based Predictive
- **FAULT DETECTION:** Corrective Deferred or Opportunistic
- **SCHEDULED**
- **OPERATIONAL TIME WINDOWS:** Type 1 (LBSPM), Type 2 (SBSPM), Type 3 (ICPM)




## UNPLANNED MAINTENANCE (UPM)


- **FAULT DETECTION:** Corrective
- **UN-SCHEDULED**
- **OPERATIONAL TIME WINDOW:** Type 4 (UPM)



# IFMIF-DONES – A Challenge beyond Physics



# How to get involved in DONES



## **DONES website**

Call for Tenders Section

<https://ifmif-dones.es/ifmif-dones-spain/call-for-tenders/>



## **Fusion for Energy**

Industry Portal

<https://industryportal.f4e.europa.eu/>



## **Belén del Cerro**

Spanish ILO (Industrial Liaison Officer)  
for ITER and IFMIF-DONES

[anabelen.delcerro@cdti.es](mailto:anabelen.delcerro@cdti.es)



## **Industry Office**

Big Science Industry  
Association

[info@industryoffice.org](mailto:info@industryoffice.org)



**DONES**

[www.ifmifdones.org](http://www.ifmifdones.org)